



ITWorkup - Level up your IT!

Waterfall Office Park, 28 Augrabies Rd Vorna Valley, Midrand, 1685

Generated: 2026-10-30 13:44

The product information provided is for reference purposes only. Technical specifications, photos, descriptions and prices may change without prior notice. The manufacturer and seller are not responsible for possible data discrepancies or typographical errors. We recommend checking the current information before purchasing.

itworkup.co.za | sales@itworkup.co.za | +27 (11)541-9950

The product information provided is for reference purposes only. Technical specifications, photos, descriptions and prices may change without prior notice. The manufacturer and seller are not responsible for possible data discrepancies or typographical errors. We recommend checking the current information before purchasing.

itworkup.co.za | sales@itworkup.co.za | +27 (11)541-9950



**APC NetShelter
Metered Rack
PDU, 0U, 3PH,
22kW 230V 32A
or 17.3kW 230V
24A, x30 C13
and x12 C19
outlets, IEC 309
3P+N+PE cord**

Model: AP8886

Manufacturer: APC

EAN: 731304289937

Product Code: 1484686

R53,949

The product information provided is for reference purposes only. Technical specifications, photos, descriptions and prices may change without prior notice. The manufacturer and seller are not responsible for possible data discrepancies or typographical errors. We recommend checking the current information before purchasing.

itworkup.co.za | sales@itworkup.co.za | +27 (11)541-9950

APC Metered Rack Power Distribution Units (PDUs) provide active metering to enable energy optimization and circuit protection. The output and input connections are (30) C13 & (12) C19, and the cable length is 1.83m. User-defined alarm thresholds mitigate risk with real-time local and remote alerts to warn of potential circuit overloads. Metered Rack PDUs provide power utilization data to allow Data Center Managers to make informed decisions on load balancing and right sizing IT environments to lower total cost of ownership. Metered Rack PDUs include real power monitoring, a temperature/humidity sensor port, locking IEC receptacles, and ultra low profile circuit breakers. Users can access and configure Metered Rack PDUs through secure Web, SNMP, or Telnet Interfaces which are complimented by APC Centralized Management platforms using InfraStruxure Central, Operations, Capacity, and Energy Efficiency.